DISTRICT BOARD, TUMKUR.

Notification No. C. 345—30-31, *dated 6th April* 1931.

Notice is hereby given that sealed tenders will be received at the Office of the President, District Board, Tumkur, up to 2 P.M., on the 30th April 1931, for constructing a native kitchen attached to Madhugiri Travellers' Bungalow, Madhugiri Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed The work should be completed before the.....

2. The plan and the detailed estimate may be seen at the Office of the President, District Board, between the hours of 11 A.M. and 5. P.M. except on Sundays and authorised Public Holidays.

3. Tenders should be submitted on typed forms which may be obtained from the Office of the President. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. (100) one hundred only in cash or Government Promissory notes, as earnest money and be superscribed "Tender for constructing a native Kitchen attached to the 3rd Class Travellers' Bungalow, at Madhugiri", in default of which tenders will be rejected.

5. The final acceptance of the tender will rest with the President, District Board, Tumkur, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond ; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted, will be posted on the Notice Board in the President's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The rates should be written legibly both in figures and words without correction.

10. The contractor will not be allowed to claim enhanced rates after the submission of the tender at any stage.

11. The decision of the President, District Board, will be final and legally binding on the Contractor in case of disputes about the rates qualities and quantities of work.

ABSTRACT OF THE ESTIMATE.

Serial No.	Items of Work	Quantity	Per	Rate
1	Earthwork, excavation and filling basement	16	C.yds	
2	Burnt stone in mud, filling foundation and basement	567	C.ft.	
3	Burnt brick in clay—Superstructure	821	,,	
4	Burnt brick in mortar—Arch Work	10	,,	
5	Burnt brick sides of doors and windows	197	,,	
6	Burnt stone slabs dressed and fixed	118	S.ft.	
7	Plastering with chunam	19·65	Sqr.	
8	Whitewashing—Two coats	19·65	,,	
9	Pointing with chunam	1·27	,,	
10	Providing mortar and pestle stone	L. S.		
11	Honne wood work wrought and put up with wood-oiling	37·70	C.ft.	
12	Roofing with 1st class Tumkur tiles, Mangalore pattern on teak reepers, etc.	7·40	Sqr.	
13	Ridge tiles set in mortar and cement pointing	29	R.ft.	
14	Ventilating tiles	4	Each	
15	Teakwood battened door with iron work and chocolate painting, etc., complete.	101	S.ft.	
16	Teakwood battened windows with iron bars, etc., complete with chocolate painting.	9	S.ft.	
17	Teakwood glazed ventilators with iron bars, iron works, etc., complete with chocolate painting.	22	,,	
18	Flooring with 1st class Mangalore tiles over 3" concrete and cement pointing.	2·73	Sqr.	
19	Binding wall over gable	43	R.ft.	
20	Constructing cistern wall with cement plastering and providing iron pipe 2' long.	L. S.		

D. S. MALLAPPA.
President, District Board.